

# Aerial Splicing Chassis Package



## Package Price Includes: Aerial Splicing Chassis

- 44' UTEM Non-Insulated Aerial
- 10' x 8' Splicing Lab
- Honda Generator

## 2024 Ford F-550 XLT

- Single Cab
- 4X4
- Automatic Transmission
- 6.7L Diesel Engine

Additional Options Available Upon Request



# Splicing Lab Interior



### **Aerial Specifications:**

- UTEM UTLN41 Non-Insulated, Articulated/Telescopic Aerial Device
- Truck Mount Pedestal
- Curb Side Pedestal Access Per Dwg. 1282
- Pedestal Riser For UTLN41 ASC W/ EH OR HE Hyd
- Turret, Stowed Height of 10 ft. 4 in. (3.15m)
- UTLN41 Aluminum Inner Boom With Hydraulic Leveling
- Steel Lower Boom
- Side Mount Channel Platform Support
- Proportional Upper Controls
- Proportional 5-Spool Valve (Hydraulic Leveling)
- 540 Degree Non-Continuous Rotation
- 24x24x42 Fiberglass Basket W/ Center Walk Thru & Door
- 350lb. (159kg) Platform Capacity
- Soft Vinyl Basket Cover (Fits 24x24 Basket)
- Emergency Lowering for "HE" Hydraulics Only
- 120V Tool Outlet at Platform
- UTEM White Powder Coat
- Remote Lower Control W/ 35' Cord

### **Extreme Fiber Optic Splicing Body**

- Fiber Optic Splicing Truck Body- (Aluminum) 10' L x 8'W 120" L x 96"W x86.5"T (76.25" Interior Height)
- R-11 Insulated Walls & Ceiling
- One Egress Window- (Curb-Side)
- Qty 2 Cable Entry Doors, (One Curb-Side & One Rear)
- Rooftop air conditioner 13,500 BTU w/ heat strip
- Rubber floor mat
- Cross isle "H" table counter top with storage
- Curb-side countertop, (black surface)
- Street- side counter top full length, (black surface)
- Black Rubber Counter Top Mats
- Cabinets/Shelving Under Counter Tops
- Parts storage bin, mounted above countertop, (street-side)
- Honda Generator & Cover
- Fire extinguisher, 2Lb
- Exterior, LED scene lighting (Qty 2 Curbside / One Rear)
- Exterior, LED strobe lighting
- 120VAC receptacles, Interior (Qty 4) quad plugs

### **Installation**

- Install Aerial Mounting Hardware On Chassis Frame
- Install Rear Underframe Torsion Bar
- Fabricate Deck To Mount Aerial & Genset
- Install Aerial
- Prep & Install BRB Splicing Body Wire DOT Body Lights
- Install PTO & Pump
- Wire PTO For Start/Stop
- Install Hydraulic Hoses
- Fabricate & Install Tailshelf
- Fabricate & Install ICC Bumper
- Fabricate & Install Boom Rest
- Fabricate & Install Arch Type Grab Handle
- Fabricate & Install Cable Step
- Fabricate & Install Access Step For Bucket
- Fabricate & Install T-Bar Bucket Support
- (Qty 2) Amber LED Beacons ...Location TBD
- (Qty 4) Surface Mount Strobes (Two Mounted @ Rear/Two On Front Bumper)
- Install (Qty 2) Mud Flaps
- (Qty 2) Wheel Chocks
- Fire Extinguisher, 5#
- NonSkid Tailshelf Surface
- Install Honda Generator & Cover
- Install Factory Back Up Camera
- Back UP Alarm, 97db
- Installed DOT Reflector Kit
- Paint Deck & Tailshelf Black Includes Labor To Install

### **Chassis Specifications**

- 2023 Ford F550
- Super Cab
- 4x4
- 6.7L Power Stroke Turbo Diesel
- TorqShift 10-Speed Automatic Transmission
- 19,500 # GVWR
- Rear View Camera Prep Kit